

5

Field Hugaton
State Kansas County Kearney
Company Stanolind Oil & Gas
Farm Edwards Gas Unit Well No. 1
Sec. 22 Twp. Blk. 23S Range Survey 38W
fr N fr E fr S fr W
of C SE $\frac{1}{4}$

Contractor Noble Drlg.

Remarks

Comm. 8-16-55 Comp. 9-21-55
Elev. 3354 Gr. T. D. 2789 P. B. 2747
Pay 3356 DF 2628-49 - 2604-82
2706 - 2738

I. P. 1,107 mcf R. P. 369 #
Casing Record: 13 3/8 7
20 10 3/4 5 1/2 2788/900
16 8 5/8 914/400

Log by Co

LOC	Tops
<u>RTD 2789 m</u>	<u>Ken-Kin 2614</u>
<u>BR Log</u>	<u>Winf 2664</u>
	<u>Lowmide 2728</u>
<u>5 1/2 2788/900</u>	<u>H. Riley 2760</u>
<u>W DCT</u>	

AUG 31 1955

RUOT CO to 2780
24/2760-64, km/500 km/1000
5 1/2 2000 km/1000 swab 15 gph
for 12 hrs. n.g.
run thg wph @ 2747 & seg
W/300 ft WDC

SEP 7 1955

p. 24/2754-38 18/2729-32
12/2717-19 24/2706-10
Grant Kern/500 ft/3000
ad/6000 Kern/1000 8 hr BD
442 mcf W 125 g Kern/hr
24 hr. BD g 445 mcf. W 10 g

pers

613202

P 1 4 1955

set bridge plug 2695

P 48/2664/72 24/2678-82

ali chr g. treated

Kero/500 fine/3000 sd/6000

Kero/1000

36 hr BD

268 muf w 20 g

Kero P.H.

bridge plug 2655-

P 12/2647-49

12/2640-42 - 36/2628-34

48/2616-24 - Kero/500 fine/4000

sd/8000# Kero/2800 12 hr BD.

1, 109 muf w 75 g Kero/hr.

42 hr BD. 871 muf with
15 g Kero per hr. Blowing

& drying

SEP 21 1955 -

Once all plug. comple

20 min of fl-guages, 107 muf

SIP 369 #

plug back to 2747.

4