

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

State of Kansas
Wichita, Kansas
Loc. 100 N/C SL SW

API No. 15 — 075 — 20,295
County Number

Operator

W. B. Osborn Operator

Address

P. O. Box 17968 San Antonio, Texas 78286

Well No.

#1

Lease Name

Victor

Footage Location

1420 feet from (N) (S) line 1320 feet from (E) (W) line

Principal Contractor

Service Drilling Company

Geologist

Walter Ralls

Spud Date

6.30.79

Total Depth

2665

P.B.T.D.

2658

Date Completed


7.4.79

Gas Purchaser

Unknown

County Hamilton

640 Acres



Locate well correctly

Elev.: Gr. 3354'

DF KB 3361'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	23#	340	Class "H"	225	3% CC
Production	7-7/8	5-1/2	14#	2662	Litewate	500	
					Pozmix	200	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2630-40
Size	Setting depth	Packer set at			
2-3/8	2660'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gals 15% acid, broke @ 1600#, pumped in @ 150#. Fraced w/135 sxs 20/40 sand @ 485 bbls fluid, rate 10 BPM	2630-40

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
1st production test 7.30.79		Pumping water through tubing, flowing gas up annulus			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	0	50	55	---	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
Vented during test			2630-40		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator W. B. Osborn Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Victor		Dry gas
S 11 T 23 S R 39 W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			DEPTH
Sand, gypsum	0	340	
Sand, gypsum, shale & lime	340	1383	
Sand, shale, lime	1383	2371	
Shale, lime	2371	2416	
Shale, lime	2416	2665	
	T.D.	2665	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Signature Production Manager Title December 12, 1980 Date		