

15-075-20304

State Geological Survey
KANSAS DRILLERS LOG
 WICHITA BRANCH

S. 22 T. 23S R. 39 ^K W
 Loc. C SW/4
 County Hamilton

API No. 15 — 075 — 20,304
 County Number

Operator
 W. B. Osborn Operator

Address
 P. O. Box 17968, San Antonio, Texas 78286


Well No. 1 Lease Name Jeanne

Footage Location
 1320 feet from (N) (S) line 1320 feet from (E) (W) line

Principal Contractor Service Drilling Co. Geologist Walter Ralls

Spud Date 7.29.79 Total Depth 2620 P.B.T.D. 2618

Date Completed 8.15.79 Oil Purchaser ----



Elev.: Gr. 3339
 DF KB 3346

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	24#	340	Class H	225	3% CC
Production	7-7/8	5-1/2	14#	2620	Pozmix	650	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3/8" - Jet	2588-98

Size	Setting depth	Packer set at
2-3/8" OD	2618	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac - 485 bbls of KCL water, 40,000# of river sand @ 10 BPM - Avg. press 100 psig	2588-98

INITIAL PRODUCTION

Date of first production 1st Production Test 9.17.79	Producing method (flowing, pumping, gas lift, etc.) Pumping water up tubing, flowing gas through annulus
RATE OF PRODUCTION PER 24 HOURS	Oil --- bbls. Gas 400 MCF Water 10 ⁴ bbls. Gas-oil ratio --- CFPB
Disposition of gas (vented, used on lease or sold) Vented during test	Producing interval(s) 2588-98

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Well No. 1	Lease Name Jeanne	Gas
S 22 T 23SR 39 ^{EX} _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand, Gypsum	0	340		
Sand, Gypsum	340	1623		
Sand, Shale, Lime	1623	2571		
Shale, Lime	2571	2615		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Production Manager
	Title
	October 23, 1979
	Date