

23-23. 4W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- S & K OIL COMPANY
Farm- Blake No. 10

SEC. 23 T. 23 R. 4W
SW NW SE

Total Depth. 5008
Comm. 5-8-55 Comp. 6-30-55
Shot or Treated.
Contractor. Buick Drilling Inc.
Issued. 8-24-57

County Reno

KANSAS



Elevation. 1464 G.L.

CASING:
13 3/8" 306'
10 3/4" 700'

Production. SWDW

Figures indicate Bottom of Formations.

Drill Stem Test:

#1 3346-86 Open 1 hr.,
Weak blow throughout
test. Recovered 25 ft
of slightly gassy mud
with a few "specks" of
oil. IFP 0#, FFP 0#,
BHPSIP 34" in 20 mins.

sand, gravel	165
shale blue	475
salt, shells	490
anhydrite, gyp	550
gyp, lime, shells	702
shale, lime, sand	895
sand, lime	940
lime, shale	970
lime	1020
lime broken	1205
lime	1300
shale, lime	2568
lime	2870
shale, lime	3200
lime	3210
shale	3253
chert, lime	3263
chert	3285
chert, lime	3386
lime	3425
lime cherty	3450
chert	3460
lime	3485
shale, lime	3520
shale	3605
lime, chert	3625
cherty lime, shale	3660
shale, lime	3750
sand, shale	3785
shale, lime	3815
shale	3820
lime Arbuckle	3845
lime	3985
lime, chert	4035
lime	4170
lime, chert	4315
lime	4450
Granite Wash	5008

Tops: K.B.		
Brown lime	2538	
Lansing-Kansas		
City lime	2590	
Mississippian	3252	
Kinderhook shale-		
Base of Miss. lime	3603	EL. Log.
Maquoketa (Sylvan)		
shale- Base Hunton	3640	" "
Viola lime - Base		
Maquoketa	3720	" "
Simpson Formation-		
Base Viola lime	3745	" "
Arbuckle Dolomite -		
Base of Simpson	3823	" "
Granite Wash"- Base		
Arbuckle	4449	" "

Cable tool to run
4 1/2" cement lined
tubing to bottom
Total Depth