


KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Union National Bank Bldg, Wichita, Kansas

LLOYD, FROST AND STUDY
Haury No. 3-C

SEC. 1 T. 23 R. 4 W
NE corner NW $\frac{1}{4}$

Total Depth. 3338
Comm. 12-2-33 Comp. 1-12-34
Shot or Treated.
Contractor. Lloyd, Frost and Study.
Issued. 2-17-34

County. Reno.



CASING

12 $\frac{1}{2}$ " 485' 65/8" 3246'

Elevation 1455

Production. 904 bbls.

Figures Indicate Bottom of Formations

sand	210	lime hard	2880
shell	212	shale	2890
shale	330	lime hard	3000
shells	335	broken shale	3018
shale	346	sticky gumbo	3028
shale and lime shells	485	shale	3040
gyp hard & lime	492	shale & lime shells	3134
broken shale	575	shale sticky	3160
shale and lime shells	865	lime	3178 SLM
broken shale	970	Var. col shale	3236
broken lime	998	chat	3338 T.D.
shale & lime shells	1200		
shale	1575	1/4 Million cu ft gas	3260-3263
lime	1600	Top Pay	3310-3325
shale & shells lime	1680		
broken shale	1778	Production 1st 24 hours	904 bbls.,
shale blue	1816	Rock pressure	700#
sticky gumbo	1846	2 $\frac{1}{2}$ " Reg. Tubing. No packer.	
shale	1935	6/40# Republic Electric Weld Tubing.	
broken lime	2038	Hinderliter Control Head.	
lime	2078		
shale	2123	Chat	3236-3338.
lime ' shale break	2192	Pay topped	3310 to 3325
broken lime	2270		
lime	2320		
shale and shells	2405		
lime	2419		
broken lime	2472		
lime	2542		
lime and shale break	2600		
lime	2665		
shale sdy	2690		
lime hard	2750		
shale sdy	2760		

3236
1455
-1781