


KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas.

BARNSDALL OIL COMPANY.
 Martha Sabin No. B-6

SEC. 11 T. 23 R. 4W.
 Sec NE
 330' W of E.L. 330' N of SL

Total Depth. 3623
 Comm. 12-19-34 Comp. 1-11-35
 Shot or Treated. 1000 gal.
 Contractor. Arrow Drilling Co.
 Issued. 2-2-35

County. Reno.



CASING.

15 1/2" 164' 7" 3609'
 12 1/2" 599'

Elevation. 1492

Production. Pot. 1693B.
 after acid.

Figures Indicate Bottom of Formations.

sard ard shale	166
shale and gyp	460
salt	514
shale and shells	601
shale and gyp	650
shale and shells	1170
shale	1217
shale and shells	1316
shale	1650
lime broken	1720
shale	1859
lime	1925
shale	1945
shale and shells	1991
shale and lime	2089
lime broken	2237
shale	2495
lime K.C.	2552
shale	2571
lime	2760
shale blue	2790
lime	2805
shale	2820
lime	2933
oolitic lime	3006
lime and shale	3058
lime	3088
lime and shale	3128
shale	3277
chat and shale	3298
chat	3493
chat and shale	3522
lime	3525
shale	3558
shale and shells	3604
Hunton lime (cored)	3615 Top of Hunton at '3607'6"
lime	3623 Total Depth.

3265
 1492
 -1773