

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Bldg, Wichita, Kansas

WILCOX OIL AND GAS CO.
 F.F. Neufeld No. 2.

SEC. 12 T. 23 R. 4W.

~~SE SW NW~~
 NW SW NW

corrected 3-20-37

Total Depth. 3621.
 Comm. 2-1-35 Comp. 3-9-35.
 Shot or Treated. 1000 gal acid.
 Contractor. C.C. Callan.
 Issued. 4-6-35.

County. Reno.



Elevation. *1488*

CASING.

15 $\frac{1}{2}$ " 181'
 12 $\frac{1}{2}$ " 541'

Production. Pot. 1433 B.

Figures Indicate Bottom of Formations.

sand and shale dark soft	181	shale dark soft coring.	3614
shale dark soft	460	shale dark soft	3617
salt white	465	lime dark med	3619
lime & shells dark med	517	lime core showing of oil	
broken lime dark med	551	Hunton lime dark med	3621
shale and shells dk med	1629	Total Depth.	
shale soft	1730		
sand white soft	1743		
shale and shells dark soft	1832		
shale and shells dark soft	2161		
shale dark soft	2176		
shale and sand	2277		
shale and sand dark soft	2447		
shale dark soft	2532		
lime white hard	2666		
shale dark soft	2710		
lime dark hard	2803	K.C. lime.	
shale dark soft	2820		
lime dark hard	2888		
lime and shale dark med	2902		
shale hard soft	3005		
lime dark hard	3035		
shale dark soft	3139		
lime dark hard	3179		
shale dark soft	3215		
broken lime dark med	3287		
chat light med	3341		
shale dark soft	3349		
chat dark med	3355	oil and gas.	
chat dark med	3435		
shat and lime dark med	3464		
lime dark med	3484		
shale dark soft	3487		
lime dark hard	3514		
sand dark hard	3519		
shale dark soft	3600		
shale dark soft	3610	coring.	

3280
1488
-1792