


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

WILCOX OIL & GAS CO.
F.F. Neufeld No. 4.

SEC. 12 T. 23 R. 4W
SE SW NW
330' fr E & SL

Total Depth. 3420'
Comm. 3-21-37 Comp. 4-15-37
Shot or Treated.
Contractor. Company Tools
Issued. 7-17-37

County. Reno



CASING:
12 1/2" 217'
10 " 504'
6 5/8" 3420'

Elevation. 1490

Production. Pot. 1513 B.

Figures Indicate Bottom of Formations.

surface sand	63
sand	170
shale	292
shale & shells	457
shale	465
shale & shells	504
brkn lime	550
shale & shells	2140
brkn lime & shale	2205
shale & lime	2740
K.C. limo	2757
lime	2829
shale	2850
lime	2935
lime & shale	3152
shale & shells	3202
shale & lime	3250
chat	3352
chat sft, showing oil	3365
chat	3420
Total Depth.	

3250.7
1490.
-1760

Production 1st 24 hrs Natural 120 B.
Production 1st 24 hrs after shot Pot. 1513 B.