


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

OLSON OIL COMPANY.
M.E. Sabin No. B-4

SEC 13 T. 23 R. 4W.
C SE SW
660' fr S.L. 660' fr E.L. SE¹/₄

Total Depth. 3374
Comm. 6-19-36 Comp. 7-17-36
Shot or Treated. 1000 gal acid.
Contractor. Olson Drilling Co.
Issued. 9-5-36

County Reno.



Elevation. 1469

CASING

13" 250' 7" 3274'

Production. 84 B.O. 1BW
& 7 M.C. ft gas

Figures Indicate Bottom of Formations.

sand	24	sand	2501
sand and shells	250	lime and sand	2523
lime shells	327	broken shale	2532
shale and sand	350	lime	2552
broken salt	481	shale and lime shells	2621
anhydrite	542	broken lime	2690
anhydrite and shale	620	shale and lime	2761
shale and shells	710	lime	2832
broken lime & shale	782	shale	2859
lime and shale	879	lime	2951
shale and shells	964	broken lime	3014
lime & broken shale	1027	shale	3051
broken lime shale and		lime	3065
red rock	1101	broken lime	3075
broken lime and shale	1130	shale & lime shells	3115
shale and shells	1175	shale	3135
shells	1189	broken lime	3150
broken shale	1260	shale	3157
shale and broken lime	1325	shale	3193
broken lime and shale	1346	V _a r. colored shale	3248
red rock	1354	lime	3253
shale	1519	chat	3374 Total Depth.
red rock	1531	4 M. gas 3307-3312	
shale	1570	slight increase of gas.	
shale and lime shells	1669	First oil 3337	
shale and lime shells	1733		
shale	1817		
broken shale	1865		
broken lime and shale	1902		
shale	2014		
lime	2044		
broken lime	2064		
lime and shale	2100		
broken lime & shale	2149		
shale & broken lime	2190		
broken shale	2267		
broken lime	2331		
lime	2417		
broken shale	2454		

3253
1469
-1784