

OLSON-SHELL PETROLEUM CORP.
 M. B. Blake. No. 3.

SEC. 23 T. 23 R. 4W.
 C SW SE
 610' SL 660' WL

Total Depth. 3370'
 Comm. 12-2-34 Comp. 2-26-35
 Shot or Treated.
 Contractor. Olson Drilling Co.
 Issued. 3-23-35.

County Reno.

CASING.

16" 256' 85/8" 3268'
 5 1/2" 3328'

Elevation.

Production. Flow 293 B.O.
 24 Hr. Pot. test

Figures Indicate Bottom of Formations.

clay	16	lime	3107
sand and clay	64	shale	3123
sand	188	lime	3142
lime	257	shale	3167
lime	265	shale	3193
lime and shale	478	shale and lime	3221
shale and shells	540	broken lime	3241
lime	556	shale and false chat	3252
shale and shells	590	chat	3268
anhydrite & gyp	640	chat	3305
broken lime	671	7,420,000 gas at 3280	
shale	700	10 Mil gas at 3305	
lime	745	16 Mil gas at 3318	
shale & shells	790	16,300,000 gas at 3321.	
lime hard	809	chat	3321
shale and shells	839	chat	3340
No log	956	show oil 3336-40.	
shale and shells	979	30' oil 300' oil 8 hrs.	
broken lime	1000	chat	3344
shale and shells	1210	chat and lime	3349
broken lime	1245	lime	3353
shale and shells	1266	lime and chat	3356
shale	1282	hole filling with oil	3352'
lime	1349	lime and chat	3360
broken lime	1391	chat	3370
shale and shells	1530	flow 293 bbls oil and no water	
shale	1595	24 hours Pot. test.	
broken lime	1650		
lime	1695	Total Depth	3370
broken lime	1735		
broken lime	1782		
shale and shells	1886		
lime and shale	1964		
lime	1979		
shale	1984		
lime	2011		
broken lime	2086		
shale and shells	2129		
lime hard	2213		
broken lime	2234		
lime	2300		
broken lime	2359		
shale and shells	2378		
lime	2383		
lime	2397		
shale	2426		
lime	2472		
shale	2490		
lime	2510		
broken lime	2526		
broken lime	2554		
lime	2587		
broken lime	2615		
lime	2646		
2646 equals 2648 SLC			
broken lime	2708		
lime	2860		
lime	2935		
lime	2981		
shale slate lime	3011		