


KANSAS WELL LOG BUREAU - K. E. S. GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

AMERICAN PETROLEUM CORP.
Hubert Wilson No. 2

SEC. 23 T. 23 R. 4N.
NE SW SW

County. Reno.

Total Depth. 3607
Comm. 12-11-34 Comp. 1-20-35
Shot or Treated.
Contractor. Olson Drilg Co.
Issued 3-2-35



CASING.

15 1/2" 168'8" 7" 3597'5"
12 1/2" 495'4"

Elevation.

Production. 4355 bbls after
acidizing.

Figures Indicate Bottom of Formations.

sand	98	chert and lime	3272
sdv shale	230	dolomite white fine	3275 oil
broken shale and shell	400	cherty line white	3283 stain
salt	450	lime white	3296
shale	455	dolomite porous	3299
broken shale and shells	474	oil stain.	
shale and lime shells	495	lime white	3301
shale	500	dolomite and lime	3304
shale and lime	512	lime white	3305
lime shells	533	dolomite brown	3306
sand lime shells	590	dolomite and lime	3311
shale and shells	634	slightly oil stain gas show on pits	
shale	710	dolomite	3317
shale pink and shells	720	dolomite brown oil stain	3322
lime and shale	837	lime white oil stain	3326
shale and shells	870	increase in gas	
sand	920	dolomite	3331
shale and lime	991	Highly saturated increase in gas.	
broken lime and shale	1070	dolomite good saturation	3332
sdv lime white	1087	lime	3339
lime and broken shale	1123	dolomite	3352
broken lime and shale	1270	dolomite brown	3378
lime grey	1344	pay zone.	
shale and shell blue	1378	dolomit chert	3385
lime and shale	1500	dolomite chert & limestone	3392
shale and shells	1552	limestone and chert	3399
shale and lime shells	1730	dolomite	3400
broken lime	1790	dolomite limestone & chert	3440
lime hard	1800	limestone & chert	3460
shale and lime	1850	limestone	3485
shale blue	1880	dolomite	3498
lime	1910	Base Miss Line	3485
shale and shells grey	1993	shale Kinderhook	3590
shale and lime shells	2060	shale	3594
lime and shale	2129	Misner	3596
broken lime and shale	2302	Hunton	3607
lime	2352	TD.	
broken lime	2396	GEOLOGICAL TOPS.	
broken lime shells	2480	FT. Riley	795
shale and lime shells	2538	Topeka	1995
shale	2545	Lansing	2565
lime	2690	Kansas City	2904
sdv lime and shells	2710	chat	3255
lime	2720	Kinderhook	3498
broken lime and shale	2775	Misner	3594
broken lime	2795	Hunton	3596
lime hard	2811	ACID TESTS	
lime	2973	500' 2 degrees	
cored 2910-18 good saturation		1000' 2 degrees	
lime	3059	1500' -	
lime and shale	3156	2000' 1 degree	
shale and lime	3216	2500' -	
sticky shale	3230	3000' 1 Degree	
shale	3252	3405 -	
lime	3255		
top chat	3255		