


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Bldg, Wichita, Kansas.

AMERADA PETROLEUM CORP.
 H. Wilson No. 3

SEC. 23 T. 23 R. 4W.
 SE NW SW

Total Depth. 3629 P.B. 3619
 Comm. 2-2-35 Comp. 3-20-35
 Shot or Treated.
 Contractor. Olson Drilling Co.
 Issued. 4-27-35.

County. Reno.



CASING.

15 1/2" 251' 7" 3596'
 12 1/2" 527' 3" upset tubing 3584' 2"

Elevation.

Production. 1475 B. Pot
 test after acidizing.

Figures Indicate Bottom of Formations.

shale and shells	251	cored no show	2904-2922
shale and shells	400	shale lime	3045
salt	470	shale	3160
shale and shells	580	shale lime	3208
lime	600	shale	3260
shale and shells	640	chat	3485
shale and lime	711	shale	3500
shale and lime shells	977	shale lime	3512
shale and lime	1115	shale	3590
shale and shells	1366	correction	3588
shale and shells	1625	cored 3580-3595 shale.	
shale and shells	1830	cored 3595-3602 shale	
shale lime shells	1906	cored 3602-3607 SIM	
shale and shells	1994	1' Hunton 2' Misner	
shale lime shells	2005	Hunton	3629
lime	2030	Total Depth.	
shale and shells	2038	SIM 3607	
shale and lime	2092	Plugged back	3619
shale and shells	2146		
shale and lime	2204		
lime brown	2245		
shale and lime	2395		
shale and shells	2472		
lime and shale	2606		
lime	2680		
lime and shale	2759		
broken lime	2808		
lime	2828		
lime hard	2904		