

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. CNW NE Sec. 34 T. 23 R. 4W

Casing Record,

10" Farm. Hiram Baughman
 20" 8 $\frac{1}{2}$ " 3278'11" mpany, Barnsdoll et al.
 15 $\frac{1}{2}$ " 234'2 65/8" Centr. Olson Drlg Co.
 12 $\frac{1}{2}$ " 501'1 53/16" Comm. 7-18-32
 Total Depth. 3390 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.

County. Reno.

No. 1

Comp. 8-30-32



Elevation.

Figures Indicate Bottom of Formations.

Date Issued. 9-24-32

Initial Production

Flowing 5 bbls oil and 5 bbls water per hr 6,000,000 Gas.

Formation	Depth	Formation	Depth.
surface	12	chert and lime	2209
sand	40	lime and broken shale	2267
shale grey	162	lime and shale blue	2450
shale hard	170	sdv blue shale	2513
shale blue	220	sdv shale lime shells	2600
shell and hard shale	244	lime hard and shale blue	3005
shale blue	435	hard rock and shale grey	3039
sand	466	lime and shale	3120
sand shale and shells	495	shale and broken lime	3160
shale blue	505	lime shells grey shale	3200
lime	610	variegated shale	3257
shale and shells	650	variegated shale and lime	
lime shells and sand	705	shells	3282
red shale and shells	790	variegated shale and lime	
sand white	845	shells(cored)	3292
lime blk	880	chert	3362
shale blue and lime shells	910	chert and white lime(cored)	3367
lime white	958	chert and white lime	3390
lime shells and sand	1113	T.D.	
shells white and brown shale	1180	Note* After running 8 $\frac{1}{4}$ " the 12 $\frac{1}{2}$ " casing	
shale and lime shells	1240	was found to be parted. The 5th	
shale lime and red rock	1305	joint was broken off in the collar	
lime white and sand	1335	5 jts or 100'10" of 12 $\frac{1}{2}$ " casing were	
shells green and red shale	1390	pulled and cemented(thru 1" pipe)	
shale blue and shells	1495	w/223 sxs. Portland cement between	
broken lime and blue shale	1558	12 $\frac{1}{2}$ " and 8 $\frac{1}{4}$ " casing.	
shale blue and shells	1605		
shells blue and brown shale	1850		
sand and shale	1980		
broken lime and shale blue	2013		
sdv lime and shale blue	2190		