

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

BARNSDALL OIL COMPANY ET AL.
H. Baughman No. 2

SEC. 34. - T. 23 R. 4W.
SE SW NE
330' N 330' W. of SE corner
of lease $W\frac{1}{2}$ NE $\frac{1}{4}$

Total Depth. 3690 P.B. 3516
Comm. 2-21-35 Comp. 4-20-35.
Shot or Treated,
Contractor. Noble Drilling Co.
Issued. 5-25-35

County. Reno.

CASING.

16" 205' 7" 3606'
18" 643'



Elevation.

Production. 303 bbls 24 H.
Pumping Potential.

Figures Indicate Bottom of Formations.

sand	135
shale and shells	206
shale	360
salt and lime	499
shale	505
lime and salt broken	508
anhydrite and salt	528
anhydrite and lime	575
lime and shale	602
shale	645
lime	780
lime and shale broken	930
red bed	940
lime broken	1065
shale and lime	1400
shale and shells	1680
shale and lime	1990
lime	2025
shale and shells	2093
lime shale broken	2152
lime broken	2280
shale and shells	2316
lime and shale broken	2379
shale blue	2437
sand	2485
shale broken	2560
lime	2942
shale	3246
cha t	3379
chat and lime	3401
lime	3435
lime hard	3454
lime	3482
shale and lime	3501
sand	3507
shale and lime	3585
shale	3606
lime	3678
shale	3685
shale and lime	3688
lime	3690 Total Depth.

Plugged back from 3690 to 3516.
with chat and cement.
Perforated 7" casing from 3370 to
3380 and from 3335-3355 with 30 shots