

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

TIDE WATER OIL CO.
C.W. Grandon No. 2.

SEC. 34 T. 23 R. 4W.
CSE SW.
660' N & 660' W of SE cor.

Total Depth. 3358
Comm. 4-9-35 Comp. 5-21-35.
Shot or Treated. 1000 gal.
Contractor. Lloyd Frost and Study.
Issued. 6-15-35

County. Reno.

CASING.

15 $\frac{1}{2}$ " 256' 85/8" 3273'
12 $\frac{1}{2}$ " 590'



Elevation.

Production. 545 B. 24 Hr.
Potential.

Figures Indicate Bottom of Formation

surface	60
sdv shale	190
shale	263
sdv shale	380
shale and shells	480
sdv lime broken gyp	545
shale and lime	595
lime and sdv shale	740
shale and lime shells	849
shale and shells	955
sdv shale	1055
shale and lime	1140
shale and lime	1235
shale and shells	1325
shale	1475
shale	1620
shale	1720
shale and lime	1815
shale	1850
lime	1905
lime and shale	1965
shale and lime	2045
lime and shale	2135
lime	2205
sand	2270
lime	2325
shale and lime	2395
shale	2440
lime	2445
lime hard broken	2505
lime	2550
shale	2555
lime (Kansas City)	2610
lime	3000
shale	3261
chat	3273
chat	3358

First shows	3296
Gas increased	3318
Approx. 4,000,000.	
more gas	3330
show of oil	3338
Spraying oil	3358

chat 3261-3273
chat 3273-3358

Tested 108 bbls 24 hours before
acidizing.

show gas 3296. Increased to 4 Mil.ft
3314-3318.
oil 3338'

3273 Steel line meas.
3358 Total Depth.