

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. CNE SE

Sec. 35 T. 23 R. 4W

Casing Record.

County. Reno.


No. 1

10" Farm. C. Gorvin
 20" 8 1/2" 3267 Company. Olson-Shell.
 15 1/2" 254 65/8" 3303 1/2 Contr. Olson Drilling Co.
 12 1/2" 53/16" Comm. 4-2-33

Comp. 5-10-33

Total Depth. 3374 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.



Elevation.

Figures Indicate Bottom of Formation.

Initial Production.

Date Issued. 6-24-33

Flow 197 1/2 B. Oil and 5 B. water in 24 hours.

Formation	Depth	Formation	Depth.
cellar	11	shale	3194
sand water	140	shale	3226
clay and shells	254	V.C. shale	3256
shale	525	chat Top of chat 3256	3279
sand	530	shale	3285
shale and shells	1150	chat and lime	3296
red rock	1215	show oil 3289 1/2	
shale and shells	1290	chat	3305
shale and lime	1318	chat and lime	3317
shale and shells	1525	3317 equals 3303 1/2 S.L.C.	
shale	1649	chat	3348
shale and lime shells	1754	chat	3374
shale	1870	show oil at 3335	
lime	1875	hole full oil and made one flow	
shale and shells	1904	at 3374	
shale	2000	5-12-33. swab and flow 150 bbls oil and	
shale and shells	2040	5 bbls water in 24 hours.	
shale	2065	5-13-33 Flow 77 1/2 bbls oil and 5 bbls.	
lime and shale	2095	water in 24 hours.	
sand	2120	5-14-33. Flow 112 oil and 5 wtr in 24 hrs.	
lime	2135	5-15-33. Flow 110 bbls oil and 5 wtr	
shale	2160	in 24 hours.	
shale and shells	2239	5-16-33. Flow 60 bbls oil and 5 wtr in	
shale	2264	24 hours.	
shale and shells	2370	5-17-33. Flow 60 oil and 5 wtr in 24 hrs.	
broken lime	2412	5-18-33 Flow 102 1/2 Oil and 5 wtr. in 24 hrs.	
lime	2425	5-19-33 Flow 50 oil and 5 wtr in 24 hrs.	
lime and shale	2445	5-20-33 Flow 115 oil and 5 wtr in 24 hrs.	
shale and gyp	2476	5-21-33 Flow 25 oil and 5 wtr in 24 hrs.	
lime shells & shale	2518	5-22-33 flow 197 1/2 bbls oil 5 bbls water	
lime shells and shale	2563	in 24 hours. flowing thru 2" tubing.	
lime shells and shale	2649		
lime and shale	2850		
lime Cored	2891		
lime	2898		
Cored Rec 5' Water.			
lime	2913		
Cored. Rec 1 1/2' Wtr.			
shale and shells	3096		
shale	3186		
lost circulation Reamed to 498.			
ran 26 jts. 12 1/2 would not set, pulled			
and reamed to 502. Ran 12 1/2.			