

IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 24 T. 23 R. 40 FW

API No. 15 — 075 — 20,158
County Number

Loc. C NW SE

County Hamilton

Operator
Computer Petroleum Exploration Co.

Address
1600 Broadway, Denver, CO 80202


Well No. #3 Lease Name Cook

Footage Location
1980 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Wakefield Drilling Geologist Bob Higginbottom

Spud Date 9-25-76 Total Depth 2575' P.B.T.D. 2545'

Date Completed 10-30-76 Oil Purchaser N/A



Locate well correctly
Elev.: Gr. 3353

DF KB 3361

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	20	445'	Class H	325	3% CaCl ₂
Production	6 1/4"	4 1/2"	9.5	2574	Class H	500ft ³	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		2520-30

Size	Setting depth	Packer set at
2-3/8	2551	open

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gals 15% HCL	2520-30
Frac down casing w/22,600 gals gelled 2%	2520-30
KCL water + 13,500# 20/40 sand @ 13 BPM	

INITIAL PRODUCTION

Date of first production <u>11-16-76</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>-</u> bbls. Gas <u>154</u> MCF Water <u>35(est)</u> bbls. Gas-oil ratio <u>N/A</u> CFPB
Disposition of gas (vented, used on lease or sold) <u>shut-in awaiting hookup</u>	Producing interval(s) <u>Upper Winfield</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Computer Petroleum Exploration
 DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas well

Well No. 3 Lease Name Cook

S 24 T 23 R 40 W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.
 SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite		2028'	Stone Corral	2028' (base)
Sandstone	2434'		Herrington	2434'
Sandstone	2465'		Kridel	2465'
Sandstone - 1my	2512'		Winfield	2512'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____
 Signature: W. E. Babzok
 Title: District Engineer
 Date: February 7, 1977