

WICHITA BRANCH
KANSAS DRILLERS LOG


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 26 T. 23 R. 40 E
W

Loc. NE SW NE

County Hamilton

640 Acres
N



Locate well correctly
Elev.: Gr. 3305

DF _____ KB 3313

API No. 15 — 075 — 20.1
County Number

Operator

Computer Petroleum Exploration Co.

Address

1600 Broadway, Denver, CO 80202

Well No

#1

Lease Name

Shetterly

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Wakefield Drilling

Geologist

R. Higginbottom

Spud Date

9-20-76

Total Depth

2520

P.B.T.D.

2490

Date Completed

10-15-76

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	20	325	Class H	250	3% CaCl ₂
Production	7-3/4"	4-1/2"	9.5	2520	Class H	350	10% SaH

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			1		2448-2458

Size	Setting depth	Packer set at
2-3/8"	2440'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gallons 15% Hcl	2448-2458
Frac w/24000 galls 2% KCL Water w/13,200#	2448-2458
20/40 sand Max Press - 400 psi	

INITIAL PRODUCTION

Date of first production 10-26-76		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil -	Gas 148 bbls.	Water 35 MCF	Gas-oil ratio -	CFPB
Disposition of gas (vented, used on lease or sold) Shut-in awaiting market			Producing interval(s) Upper Winfield		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Computer Petroleum Exploration DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Shetterly Gas well

S 26 T 23 R 40 E

WELL LOG SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Table with 5 columns: FORMATION DESCRIPTION, CONTENTS, ETC.; TOP; BOTTOM; NAME; DEPTH. Rows include: Anhydrite (base), Sandstone, Sandstone, Sandstone - lmy; Stone Corral, Herrington, Krider, Winfield.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received; Signature: W. E. Babcock; Title: District Engineer; Date: February 7, 1977