


KANSAS DRILLERS LOG
State Geological Survey
WICHITA, BRANCH

IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 33 T. 23 R. 40 W
Loc. C NE SW
County Hamilton



County 075 Number 20,121

Operator
Computer Petroleum Exploration Co.

Address
Box 200 Calgary, Alberta, Canada

Well No. #1 Lease Name Jantz

Footage Location
1989' feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Sedco Drilling Geologist R. Higginbottom

Spud Date November 10, 1975 Total Depth 2555 P.B.T.D.

Date Completed Oil Purchaser

Locate well correctly
Elev.: Gr. 3355'
DF KB 3365'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	310	H	250	5% CaCl ₂
Production	7 7/8"	4 1/2"	10.5#	2554	H	350	4.5% gel
					50/50 Poz	150	2% gel, 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			one	Jet .44"	2480' - 2490'

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	2513	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gals. 15% HCl acid	2480' - 2490'
14,600 gals. gelled 2% KCl water and 9000# 10/20 sand	2480' - 2490'

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Computer Petroleum Exploration Co.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.
#1

Lease Name
Jantz

gas

S 33 T 23 R 40 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Winfield top	2476		Welex Gamma Ray Acoustic Velocity Log	300' - 2548'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. E. Ewin
Signature

Drilling Engineer
Title

Apr 6/76
Date