


90142

1-43W MAP NO. 50 SEC. 15-23S-40W  
 STATE Kans. COUNTY Hamilton LOC. 100' SW of C  
 OPER. Texaco, Inc. Wichita, Kansas FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 WELL #1 FARM Nellie Henry FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
Bradshaw, Ext. ELEV. 3366 GR. LS 3371 DF 3374 KB \_\_\_\_\_  
 CO. Wakefield Drlg. Co. GEOL. \_\_\_\_\_  
 INT. \_\_\_\_\_  
 F.R. 12-3-63 SPUD 11-29-63 COMP. 1-7-64  
 TD 2560' FM. Winf. PBTD \_\_\_\_\_

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		Winf	2517	Abra jet	250A + Frac.
	I.P. <u>Ga 175,000 cfgpd + spray SW, SICP 445#/72 hrs.</u>				
Casing Record	7" @257' w/150 Sx.				
	4 1/2" @2560' w/100 Sx.				



Data Inc.

KB Log Tops:

Chase	2459	+ 915	B/Poro	2524	+ 850
Win	2506	+ 868	LTD	2560	+ 814
Poro	2514	+ 860			

C/ #1(Win)2505-39, R 34' total. 5' dns hard dol, 2' sh, 4' shly dol, 6' poro brn sdy dol, 5' brn lm, 12' sh. RTD 2560'. (Win) an log, 4 1/2" @2560' w/100 Sx. + DV tool @873' w/100 Sx. MICT, CO

2531', Abr jet Win @2517', 500A, \$ dn, Ga 240,000 cfgpd on OF pitot, Ga 295,000 cfgpd on OF pitot.  
 Frac 20,000# sd x 15,000 (3%)gel Acid x 500# walnut hulls, \$ 240 BL & AW/6 hrs. w/sli SG, SI/7 1/2 hrs. \$ 100 BAW/4 hrs. + Ga. 186,000 cfgpd. \$ & flo 60 BAW + 550 BSW/24 hrs. & Ga. 3,000,000 Cfgpd w/26 BSW/last hr. Sq @2517' w/75 Sx. CO 2531' PBTD, Abr jet 4-2" horiz slots @2517'. \$ 18 BAW w/show gas/1 hr. \$ & flo 142 BLW + 70 BSW/24 hrs. Ga 1,360,000 cfgpd, Ga. 1,700,000 cfgpd + 60 BSW/8 hrs. 12 hr. SIP 435#, Ga. 310,000 cfgpd w/360# back pressure /7 hrs. Ga 160,000 cfgpd w/425# back pressure /12 hrs. Ga 310,000 cfgpd w/360# back pressure/24 hrs. Ga 175,000 cfgpd w/lite spray SW/24 hrs. w/195# back pressure, SICP 445#/72 hrs. Winfield @ 2517' - COMPLETED (12-25-63)