

90140

7-85W

MAP NO. 50

SEC. 6-23S-40W

STATE Kansas COUNTY Hamilton

LOC. C SW NE

OPER. Sinclair Oil & Gas Co.

FT/FR _____ LINE

WELL #1 FARM Paul L. Meisel

FT/FR _____ LINE

BRADSHAW ELEV. 3468

GR. 3473 DF. 3476 KB

WAKEFIELD DRG. GEOL. _____


2800' win tst

F.R. 6/1/64 SPUD. 6/16/64

COMP. 7/14/64

TD. 2585 FM. Win

PBTD. 2562



Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		Win	2559 (only)	Slot 250 A & Frac	
	I.P. 1 hr O.F; 1,400,000 CFGPD & 20 GSW/PH				

8" @ 308 w/328 sx

4 1/2" @ 2585 w/100 sx.

Data Inc.

GR Log Tops:		
Herr	2474	+ 993
Kri	2514	+ 954
Win	2556	+ 912
LTD	2584	+ 884

Cont'd on back)

CO to 2575', log, cut slot @ 2565' (Win), Swb dry, NSO/G (wtr) 250 A, (1d-56B) Swb 56 BLW \pm 6 BSW/10 1/2 hrs. (Last 3 hrs. - 1 BSWPH. Last hr 1 1/2 BSW/PH + gas TSTM) Sq 2565' (Win) w/70 sx. PB 2562, Cut slot @ 2559' (Win) Swb dry, tst 5 hrs. NSO/G/W 250 MCA, (1d 56 B) Swb on ld. Swb dry w/SSG, Sd frac (2559) w/2000, 3% Gell Acid x 2000# sd + 100# hulls (load - 126B) Swb & F1 85 BL & AW/11 hrs (-41 BL) + Gas TWIM (Est Gas Vol 1,000,000) O. F., 1,200,000 Cfgpd + 15 GSWPH, 25/64" choke TP 30#, CP 220#/5 hrs, 1 hr. SITP 420#, 1 hr, SICP 440#, 5 hr. SITP 420#, SICP 440#/5 hrs, 1 hr. O.F. 1,400,000 + 20 GSW 1 hr., TP 20#, CP 290#, Winfield 2559, COMPLETE (7/2/64)