Records Section P1

Gulf

TYPE ★ AFFIDAVIT OF COMPLETION FORM ACO-1 WELL HISTORY

SIDE ONE

Compt. 16-23-41W

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F ____ Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C None Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # Not available EXPIRATION DATE --

OPERATOR Publishers Petroleum* API NO. N.A.

ADDRESS 500 North Broadway COUNTY ~~Hamilton~~

Oklahoma City, Oklahoma FIELD Bradshaw

CONTACT PERSON L. O. Butner PROD. FORMATION Winfield

PHONE (918) 587-6531

PURCHASER Kansas Nebraska Natural Gas Company LEASE Ochs Unit #1 (1631)

ADDRESS P. O. Box 15265 WELL NO. 1

Lakewood, Colorado 80215 WELL LOCATION NW SE


DRILLING CONTRACTOR Earl F. Wakefield 1980 Ft. from South Line and

ADDRESS ~~N.A.~~ Union Center Bldg. 1980 Ft. from East Line of (☒

Wichita, Kansas the SE (Qtr.) SEC 16 TWP 23S RGE 41 (W).

PLUGGING CONTRACTOR ADDRESS State Geological Survey WICHITA BRANCH

WELL PLAT



(Office Use Only)
KCC ____
KGS ✓
SWD/REP ____
PLG. ____

TOTAL DEPTH 2490' PBTD 2484'

SPUD DATE 7-16-62 DATE COMPLETED 7-20-62

ELEV: GR 3399' DF 3406' KB 3407'

DRILLED WITH ~~(XXXXXX)~~ (ROTARY) ~~(XXX)~~ TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE ____.

Amount of surface pipe set and cemented 139' DV Tool Used? No.

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, (Gas), Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

David P. Spencer, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

David P. Spencer

SIDE TWO

ACO-1 WELL HISTORY (XX)

OPERATOR Publishers Petroleum LEASE Ochs Unit (1631) SEC. 16 TWP. 23S RGE. 41 (W)

WELL NO. 1

FILL IN WELL INFORMATION AS REQUIRED:

W14 - 23 - 41

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
X Check if no Drill Stem Tests Run.				
Cored from 2450' to 2479'; rec. 29' of core				
Krider	2408'			
Winfield	2451'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/500 gals. 15% MCA; fraced w/16,000 gals. 5%	
jelled acid w/7300# sd & 650# walnut hulls.	2466'

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
September 10, 1963	Flowing	

Est Unated Production -I.P.	Oil	Gas	Water	Gas-oil ratio
	None bbls.	2120/D MCF	- % 0 bbls.	-- CFPB

Disposition of gas (vented, used on lease or sold): Sold

Perforations: 2466'

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	24#	139'	Regular	125	3% HA-5
Production	7-7/8"	4-1/2"	9.5#	2489'	Neat	100	Salt saturated

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
4	3/4" Jet	2466'