

9-209W MAP NO. \_\_\_\_\_ REPL. COMP. SEC. 9-23S-41W  
 STATE Kansas COUNTY Hamilton LOC. C NW/4  
 OPER. Livingston Oil Co., Tulsa, Okla. FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 WELL 1-9 FARM Geo. Inge. (HCU) (0931) FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 ELEV. 3479 GR. 3482 DF. 3485 KB \_\_\_\_\_

INT. Wakefield Drlg. Co. GEOL. \_\_\_\_\_  
 CO. INT. (61)  
 F.R. 9-25-62 SPUD 9-26-61 COMP. 9-18-62  
 TD 2560' FM. Win PBTD. \_\_\_\_\_

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		<u>Win</u>	<u>2540-60</u>		<u>OH</u>

1 P. Ga. 7,800,000 CFGPD, SIP 426#.

Casing Record  
7-5/8" @122' w/195 Sx.  
4 1/2" @2540' w/420 Sx.


*Data Inc.*

KB Spl Tops:  
 Red sd 2554 +931  
 RTD 2560 +925

Note: This well was originally operated by Hamilton Bros.  
 No DST's or Cores, No log. Drilled to 2540' and set 4 1/2" @2540'  
 w/420 Sx. DD w/3-7/8" bit to RTD 2560'. Released rig 10-2-61  
 1.274,000 CFGPD, nat. FCP 290#, No info avail. on treatment.

State Ind. OF 2-18-64, Ga. 7,800,000 CFGPD, SIP 426#, Win OH  
 2540-60. Temp. Completed 9-7-62, REPL. COMP. 3-31-64