

L. E. DOUGLASS
Durant No. 1.

SEC. 3 T. 23 R. 5W
SEc SW

Total Depth. 4024'
Comm. 5-20-38 Comp. 6-23-38
Shot or Treated.
Contractor. L.E. Douglass Drlg. Co.
Issued. 7-16-38

County. Reno



CASING:
16" 217'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand	8	lime & shale	3307
clay & sand	40	shale & lime shells	3343
red bed	125	shale & shells	3435
red bed & gyp	203	shale	3441
red rock	217	conglomerate	3451
red bed	230	shale	3458
no log	307	chat	3540
shale	675	chat & dolomite	3571
salt	762	chat	3608
GYP	975	chat & lime	3658
brkn lime & shale	1100	shale sticky	3664
shale & lime	1206	shale	3740
lime	1250	shale blue	3769
lime & shale	1440	shale	3801
brown lime	1535	Misener sand	3820
lime brkn	1625	lime, chert & some dolomite	3848
shale & lime shells	1740	lime & chert	3875
lime & shale	1945	shale	3911
shale	2026	Viola lime	3929
lime brown sft	2069	sand	3940
brkn lime	2150	cored	3950
shale & shells	2200	shale	3970
lime brkn	2247	sand hrd	3978
lime	2295	sand & sdy shale	4010
sdv lime	2335	Siliceous lime	4024
shale & lime	2365	Total Depth.	
sdv lime	2400		
lime hrd	2435		
lime	2540		
shale drk	2570		
brkn sand & lime	2592		
sand	2612		
sdv lime	2668		
lime & shale	2714		
shale	2755		
lime & shale	2930		
lime hrd	2940		
sand sft	2950		
lime brkn	2979		
lime hrd	3024		
lime	3122		
lime hrd	3133		
shale blk	3136		
lime	3190		

3820
1576 H
-2294

341
3875
1576 H
-2294

39