

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - PHILLIPS PETRO.CO.
Farm - Bernice No. 1.

SEC. 12
S W c SW

T. 23 R. 5 W

Total Depth. 4018'

Comm. 6-9-44

Comp. 7-1-44

Shot or Treated.

Contractor.

Issued. 7-15-44

CASING:

8" 394'

County.

Reno
KANSAS



Elevation. 1530

Production.

Dry

Figures Indicate Bottom of Formations.

surface sand & red bed	71
shale & lime shells	360
shale & shells	777
shale & lime shells	945
shale & shells	975
hard sand	1071
sand & lime	1195
lime & shale	1275
shale & shells	1397
shale	1510
shale & shells	2367
lime	2413
shale	2425
shale & lime shells	2486
shale & lime	2529
shale sdy & lime strks	2738
lime & shale strks	2794
lime & shale	2855
lime	2915
lime sdy & shale	2961
sand & shale w/strks of lime	3018
lime	3085
lime & shale	3135
shale	3210
shale & lime	3315
lime	3341
lime & shale	3430
chat	3563
chat & lime	3600
lime	3666
lime & shale	3839
lime & sdy shale	3865
shale & sand	3907
sand	3926
shale	3953
chert & lime	3959
sand shale & lime	3982
shale & lime	4003
Arbuckle lime	4018
Total Depth.	

Tops:

Miss. Lime 3427 DF

Kinderhook 3632

Viola 3878

Simpson Shale 3892

Simpson Sand 3897DF

Cored 3905-08; Sat. in cuttings

& core; Set packer @ 3897 &

rec 350' of salt wtr &

mud w/show of gas

Arbuckle 3986 DF

w/no shows