


plotted
33-23-9W

NADEL & GUSSMAN
McRevey No. 1.

SEC. 33 T. 23 R. 9 W
NEo SE

Total Depth. 4225'
Comm. 12-2-42 Comp. 12-23-42
Shot or Treated.
Contractor.
Issued. 1-16-43

County. Reno



CASING:
8" 159'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	0-124
shale & shells	159
shale & shells	1400
lime & sand	1455
lime	1507
sdv shale & lime-hd	1605
lime & sand	1650
shale & shells	1735
lime	1808
lime brkn	1910
lime & shale-brkn	2293
shale & shells	2585
lime & shale	2689
lime brkn	2755
shale & shells	2800
lime Topeka	2845
lime	3157
shale sdv	3193
lime & shale	3393
trace oil 3377-79	
lime	3414
lime & chert	3518
lime	3596
lime sdv	3621
shale	3661
shale hd & lime	3694
shale hd	3710
shale & lime	3787
lime & chert	3829
chert	3862
shale	4025
shale hd	4056
shale	4060
lime Viola	4075
chert	4085
lime	4125
lime & sand-Simpson	4165
shale	4196
lime Arbuckle	4225
Total Depth.	

Viola lime 4060-75 dry
Simpson 4125-65 dry
Arbuckle lime 4196-4225 dry

Hole filled w/heavy mud
from 4225-159, wooden
plug set at 159' 20 ft of
cement put in, filled w/mud
to top of surface pipe &
plate welded over top of
surface pipe

Handwritten:
4125
3862
4196

Handwritten:
3862
3787
85

Handwritten:
3862
3787
85

Handwritten:
4060
3862
198

Handwritten:
4060
3862
198