

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 155 — 20,701
County Number

Operator

Energy Exploration, Inc.

Address

Suite 606, 120 Bldg., Wichita, KS 67202

Well No.

#3

Lease Name

Harley

Footage Location

2310 feet from (N) (X) line 2310 feet from (X) (W) line

Principal Contractor

Woodman & Iannitti, Rig 3

Geologist

Curtis E. Covey

Spud Date

22SEP80

Date Completed

28SEP80

Total Depth

3470 (RTD)

P.B.T.D.

N/A

Directional Deviation

N/A

Oil and/or Gas Purchaser

Unknown

7 T. 23 R. 9 E


SW SW NW

Loc. SE SE NW

County

640 Acres

N



Locate well correctly

1741

Elev.: Gr.

DF KB 1746

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	36	240'	Common	230	2% Gel., 3% CACL
Production	7-7/8	4-1/2"	10.5	3463'	Common	85	2% Gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	55B	3263-67
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8" EUE	3256 w 12' Anch				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1 1/2% HCl & 2% HF 9 BBLs	3263-67

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
11 Nov 80	Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	17 bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	
			3263-67	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Energy Exploration, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #3 Lease Name Harley Oil

S 7 T 23 S R 9 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner Sh	3030			-1284
Douglas Sh	3052			-1306
Iatan Ls	3192			-1446
Lansing	3220			-1474
DST #1 (3255-75) 10-60-60-60, IFP 40-40#, ISIP 1159#, FFP 81-95#, FSIP 1037#, IHH-FHH 1688-1688#. Rec: 1,400' GIP, 180' Froggy Oil, 10'Mud. 109°F.				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

Clinton Covey
Signature

Exp. Mgr. EN EN
Title

7 Jan 80
Date

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

p1
D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

7- 23- 9W

State Geological Survey
WICHITA BRANCH

October 1, 1980

Company;	Energy Exploration, Inc.
Farm;	#3 Harley
Location;	SE SE NW
Section;	7-23-9W
County;	Reno
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	Sept. 22, 1980
Compl;	Sept. 28, 1980
Total Depth;	3470'
Casing;	8 5/8 @ 250 w/230 sx.
Production;	4 1/2 @ 3468 w/100 sx.

RECEIVED
STATE CORPORATION COMMISSION
OCT - 3 1980
CONSERVATION DIVISION
Wichita, Kansas

Figures Indicate Bottom Of Formations:

250	Sand & redbed
675	Sand
1375	Redbed & lime
2045	Shale
2315	Lime & shale
2950	Lime & shale
3275	Lime & shale
3470	Lime & shale

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman

K. T. Woodman

/jc