

KANSAS DRILLERS LOG

API No. 15 — 155 — 20,674
County Number

Operator
Texas Oil & Gas Corp.

Address
200 W. Douglas, Suite 300, Wichita, KS 67202

Well No. #1 Lease Name Basnett "A"

Footage Location
600' feet from (N) (S) line 2040' feet from (E) (W) line

Principal Contractor
Slawson, Rig #4

Geologist
Earl Moore

Spud Date
6-21-80


Total Depth
3848'

P.B.T.D.
N/A

Date Completed
6-29-80

Oil Purchaser
N/A

S. 6 T. 23S R. 9 EX
Loc. 600' FSL & 2040' FEL
County Reno County, KS



Locate well correctly
Elev.: Gr. 1737' 1742'
DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"		255'		300	

LINER RECORD

PERFORATION RECORD

Top, ft. N/A	Bottom, ft. N/A	Sacks cement N/A	Shots per ft. N/A	Size & type N/A	Depth interval N/A
TUBING RECORD					
Size N/A	Setting depth N/A	Packer set at N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production N/A D & A	Producing method (flowing, pumping, gas lift, etc.) D & A
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls. Gas N/A MCF Water N/A bbls. Gas-oil ratio N/A CFPB
Disposition of gas (vented, used on lease or sold) D & A, 6-29-80	Producing interval(s) N/A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Texas Oil & Gas Corp.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. #1	Lease Name Basnett "A"	
S 6 T23S R 9 XX W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOG TOPS</u>				
Herington	1456	286		
Onaga Sh	2228	-486		
Wabaunsee	2266	-524		
Topeka	2724	-982		
Heebner	3034	-1292		
Douglas Grp	3054	-1312		
Lansing	3222	-1480		
Swope	3444	-1702		
Hertha	3475	-1733		
Mississippi	3579	-1837		
Kinderhook	3594	-1852		
TD	3848			
<u>DST #1, 3370-3400' (Lansing), w/results as follows:</u>				
IFP/30": 63-63#, fair blow				
ISIP/60": 285#				
FFP/45": 73-73#, fair blow				
FSIP/90": 391#				
Rec: 30' mud				
<u>DST #2, 3582-3598' (Miss.), w/results as follows:</u>				
IFP/30": 63-52#, wk blow thru out				
ISIP/60": 63#				
FFP/60": 52-52#, wk blow, died in 45"				
FSIP/120": 63#				
Rec: 30' mud w/no shows.				
Ran O.H. Logs				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Harold R. Trapp</i>	
	Harold R. Trapp District Geologist	
	Signature	
	Title	
		July 1, 1980
		Date

DRILLERS LOG

OPERATOR: Texas Oil & Gas Corp.
200 West Douglas
Wichita, Kansas 67202

WELL NAME: Basnett 'A' #1
App. C SW SE Sec.6-23S-9W
Reno County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Doulgas Building
Wichita, Kansas 67202

COMMENCED: 6/21/80

COMPLETED: 6/29/80

RTD: 3848'

SURFACE CASING: 8-5/8" set at 255' with 300 sx cement

0' to 265' 12 1/2" Surface Hole
265' to 508' Red Bed
508' to 1343' Shale
1343' to 1713' Shale & Lime
1713' to 3848' Lime & Shale
RTD 3848'


STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the Basnett 'A' #1 log
for Texas Oil & Gas Corp.


James C. Remsberg

Subscribed and sworn to me
this 21st day of July, 1980


Mary Lou Taylor, Notary

My commission expires January 17, 1981