


CITIES SERVICE OIL CO.
Morgan No. 1.

SEC. 6 T. 23 R. 9 W
SW NW SW
990'S 330'E W $\frac{1}{4}$ Cor.
6-23-9W
County. Reno

Total Depth. 3749'
Comm. 3-15-43 Comp. 5-4-43
Shot or Treated.
Contractor. Corbett-Barbour Drlg. Co.
Issued. 6-26-43



CASING:

10 $\frac{3}{4}$ " 176' Cem.
7" 3708' Cem.

Elevation.

Production. Phy. Pot. 202 B.
No wtr

Figures Indicate Bottom of Formations.

sand & gravel	0-130
shale & shells	176
red bed	325
anhydrite	342
shale	517
shale & shells	845
shale, shells, salt	1150
shale & shells	1255
shale & lime	1445
lime	1565
sand	1575
lime & shale	1680
sand	1710
lime brkn	1800
lime	1880
lime & shale	2015
lime brkn	2085
shale	2100
lime brkn & shale	2155
lime brkn	2240
lime brkn & shale	2465
lime	2500
shale	2515
shale & brkn lime	2600
lime brkn	2700
lime brkn & shale	2725
lime	3090
lime brkn & shale	3192
lime	3620
shale	3650
shale & lime	3700
shale, sand, lime	3724
3724 Rot. TD = 3724 SIM	
lime	3749
Total Depth.	

Tops: Misener 3707
Viola 3720
Penetration 29

Loaded hole w/1500' wtr before
drlg shoe. Cleaned out to
btm, 3724; had show oil & gas;
bailed wtr load & hole filled
1800' oil

4-24-43 temp. Pot. 90 oil, no
wtr, 24 hrs

4-27-43 500 Gallons acid

4-30-43 to 5-4-43 deepened

4-30-43 to 5-4-43 deepened 3724-29