

HOLLOW DRILLING CO., INC.
Wilson No. 1.

SEC. 9 T. 23 R. 9 W.
SW¹/₄ SW

58616

Double

Total Depth. 4026
Comm. 8-1-42 Comp. 8-18-42
Shot or Treated.
Contractor, Hollow Drlg. Co.
Issued, 9-5-42

County Reno.

Rotary

CASING.

85/8" 221' cemented.

Elevation.



Figures Indicate Bottom of Formations.

Production. DRY

cellar	10
clay	70
sand and gravel	150
shale and shells	158
red rock	355
anhydrite lime	380
shale and shells	650
red rock	680
shale and shells	770
shale	805
shale and shells	910
shale	1250
salt and shale	1300
broken lime	1335
shale and lime	1605
lime	1715
shale and lime	1987
lime	2050
broken lime	2175
lime and shale	2307
shale and shells	2372
broken lime	2500
lime	2597
shale	2630
lime	3073
shale	3097
lime	3109
shale	3138
lime	3166
shale	3237
lime	3366
chert	3369
lime	3370
lime and chert	3388
lime	3540
shale and shells	3567
lime	3585
shale	3645
chert	3651
shale	3670

sharp chert	3690
lime & shale	3724
shale	3819
lime & shale	3839
shale	3844
Viola lime & chert	3868
Viola lime	3880
Dolo. and chert	3905
lime	3932
shale & sand	3966
shale	3996
lime	4026

Total Depth.

All measurements subtract 2' for
derrick floor measurements.

TOPS. Lansing	3254
Congl.	3600
Mississippi	3644
Kinderhook	3672
Masoner	3837
Viola	3841
Simpson	3923
Arb. Lime	3996