

WELL DATA SHEET

Case ZU Well No 30 Pool Zenith Date 5/90

Location W/2 Sec. 7-24S-10W County Reno State Kansas

Dist. "H"
4 From
KB to GL

Date Completed _____
 Well Elevation 1781 GL, 1785 KB
 Producing Formation _____
 From _____ To _____ From _____ To _____
 From _____ To _____ From _____ To _____

Initial Production _____ bopd _____ bwpd _____
 _____ mcfd _____ GOR _____

Initial Treatment

8 5/8 "OD Surface
 Pipe set @ 220 "
 w/ 150 sx.

6-25-85 Perf 3758 1/2 - 60 1/2 & 3740-50, acidz 200 gal;
 ON FL 2100', swab oil slum, set CIBP @ 3754, swab
 tst w/ same results

6-27-85 Sg2 perf 3740-50 w/100 sx, drill out to 3728

7-1-85 Perf 3709-13, acidz 250 gal, swab little fluid 25% oil,
 re-acidz 350 gal, 14% oil, re-acidz 1000 gal, ON FL 3200', 100% wtr,
 Subsequent Workover or Reconditioning:

Top of Cement

swab dn w/20% oil cut (very little fluid)

7-5-85 Perf 3702-05, isolate w/RBP & PKY, acidz
 500 gal, swab dn 18% oil, re-acidz 750 gal, swab
 dn 10% oil, ON FL 2600', swab dn, making little fluid

7-23-85 Set CIBP @ 3480, perf. 3460-64, acidz 300
 gal, ON FL 2600', mostly oil w/GSOG, put on
 pump

11-17-89 P & A

Present Production _____ bopd _____ bwpd _____
 _____ Gas _____ mcfd _____
 From _____ To _____
 Static F. L. @ _____ Date _____
 Pumping F. L. @ _____ Date _____

Remarks: DST 3703-375

ISIP 788 Rec 880' GIP
ESIP 778 260' Gassy HOCMSW
IFP 135-192 120' Gassy OCMSW
FFP 250-356 120' Sli gsy OCMSW
220' MSW

5 1/2 "OD # _____ Thd _____
 Gr. _____ Casing _____
 Set @ 3851 w/ 175 sx

60,000 PPM Cl