

WELL DATA SHEET

Case ZU Well No. 36 Pool Zenith Date 5/90
 Location SW/4 Sec. 6-24S-10W County Reno State Kansas

Dist. "H"
5 From
KB to GL

Date Completed _____
 Well Elevation 1802 GL, 1807 KB
 Producing Formation _____
 From _____ To _____ From _____ To _____
 From _____ To _____ From _____ To _____

Initial Production _____ bopd _____ bwpd _____
 _____ mcfd _____ GOR _____

Initial Treatment

2-17-86 Perf sqz holes 3746-48, sqz dn csg
w/150 sx, found wiper plug @ 3750, no improvement
in cmt, re-sqz thru same holes w/150 sx plus
celloflakes as LCM, drill out to 3750, TOC 3709,
set CIBP 3740

3-3-86 Perf sqz holes @ 3707-09, sqz 25 sx, TOC
3630

Top of Cement

Subsequent Workover or Reconditioning:

3-10-86 Perf Misner 3703-05, stress frac, ON
fill up 275' with 175' oil, dump 500 gal acid
and frac w/N₂ + 5000 # sd, ON FL 2000',
swab 35 BPH 20% oil, put on pmp

3-16-86 Pmp tst 454 BPD, 5% oil

Present Production _____ bopd _____ bwpd _____
 _____ Gas _____ mcfd _____
 From _____ To _____

Static F. L. @ _____ Date _____
 Pumping F. L. @ _____ Date _____

3703 L. Misner sd
3705

CIBP @ 3740

Remarks: No cmt raised behind pipe on primary
cmt job above 3750

5 1/2 "OD _____ # _____ Thd _____
 Gr. _____ Casing _____
 Set @ 3818 w/ 165 sx

TD 3820