

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

1-24-11W


Company - TRANSWESTERN OIL COMPANY
Farm - McNickle No. 5

SEC. 1 T. 24 R. 11 W
CE/2 NW NW
660' FNL 990' FWL NW $\frac{1}{4}$

Total Depth. 3736'
Comm. 2-12-45
Shot or Treated.
Contractor.
Issued. 4-14-45

Comp. 3-24-45

County. Stafford
KANSAS



CASING:
8 5/8" 332' Cem.
5 1/2" 3722' Cem.

Elevation. _____

Production. 75 BO Pot.

Figures Indicate Bottom of Formations.

sand & surface clay	165
red rock	300
red bed	332
red rock & shale	965
shale & shells	1350
lime brkn	1395
lime, shale & shells	1495
lime & shale	1575
lime brkn	1650
lime, shale & shells	1730
lime	1770
lime & shale	2365
lime brkn	2455
lime & shale	2575
lime brkn	2660
shale	2730
lime	2790
shale	2825
lime " shale	2880
lime	2925
lime & shale	3015
lime	3145
lime & shale	3170
lime	3195
shale gy	3225
lime	3245
lime brkn	3305
lime & shale	3345
lime	3400
lime & chert spots	3435
lime & chert	3455
lime	3610
lime & shale	3695
lime & sand	3706
shale	3721
lime	3724

Tops:
Lansing
Mazoner Sand
Shale
Sand
Viola lime

3330
3699-91
3691-98
3699-3703 (Odor)
3721

Total Depth w/rotary
(Correct 2' up hole for Rotary Table)
Cable Tools 3724-3736
chert 3724-30
dolomite 3730-36
Total Depth 3736