

SHELL OIL CO., INC.
A.C. Brown No. 2

Plotted
2-24-11W
SEC. 2 T. 24 R. 11W.
SW NE SW
1004' fr NL 995' EL SW $\frac{1}{4}$

Total Depth. 3761
Comm. 8-25-40 Comp. 9-23-40
Shot or Treated.
Contractor. Crow Drilling Co.
Issued. 11-2-40

County Stafford.

CASING.

13" 156'
85/8" 276'

4 $\frac{1}{2}$ " 3694'

Elevation.

Production. Pot. 21,600 B.
Bomb, no wtr. Allowed
potential 3000 B.O.

sand	40
sand	140
red bed	220
gas sand	226
red rock	260
shale & shells	306
red bed	460
lime	493
shale	566
shale lime shells	928
shale and shells	1225
shale shells & salt	1399
lime and shale strks	1484
lime and shale	1604
shale	1655
anhydrite	1690
shale and lime	1770
lime	1790
shale	1830
shy lime	1860
lime	1867
shale	1930
lime	1989
shale and lime	2110
lime	2180
shale	2236
lime	2289
shale and lime	2576
2576 equals 2573 SLC	
shale and lime	2685
shale	2728
lime	2744
lime and shale	2837
shale	2849
lime	2977
lime and shale	3063
lime	3111
shale and lime	3258
shale	3331
lime	3353
lime	3382
lime and chert	3466
lime	3580
lime and shale	3665
lime shale sand	3671
shale dark green and	
strks dolomite sand	3675
sand dolomite,	3680
fair to good porosity, trace	
live oil staining, possibly	
gas bearing.	
shale dark green to	
dark grey	3691

dolomite crystalline, light	3470-76 good por.
brown, sandy, chert 3695	no oil staining,
fair to good porosity, good	probably water
staining, good odor oil in	bearing.
cuttings.	3516-19 fair por.
dolomite crystalline, light	no show, probably
brown, trace white	water bearing.
chert 3700	3530-31. low por.
fair to good porosity, and	good live oil
oil staining, good odor	staining.
of oil in cuttings.	
limo slightly dolomitic	
hard dense finely coarsely	
crystalline chert 3718	
porosity in strks showing	
slight oil staining.	
chert, dolomite limo 3727	
showing slight to fair	
porosity and oil	
staining.	
dolomite limo crystalline 3739	
slight to good porosity and oil	
staining.	
dolomite limo white hard	
crystalline, abundant wh	
chert 3746	
strks fair porosity and	
oil staining.	
dolomite limo, white,	
crystalline, abundant wh	
chert 3756	
slight to good porosity	
and oil staining.	
dolomite limo wh hard	
crystalline, abundant chert	
3760	
strks fair porosity and oil	
staining.	
3760 equals 3761 S.L. Correction	
lime and chert 3761	
Total Depth.	

Top Viola limo 3696

Flow 176 bbls oil and no water
4 hours, flow 45 bbls oil per
hour the last 2 hours.
Acidized 4000 gal acid. Flow 134 bbls oil
and no water 2 hours after acid. oil recovered
Gauged 756,000 cu ft gas.

3356-57	slight porosity and live oil stain.
3370-71	slight porosity fair oil stain
3389-96.	slight porosity and live
	oil stain.
3407-14	slight porosity and fair live oil stain.
	fair porosity and good oil staining
3409-12	3435-37 fair porosity and
	good oil staining.

