

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

Plotted.  
E.M.


2-24-11W

DEEP ROCK OIL CORP.  
Anna Turner No. 4.

SEC. 2 T. 24 R. 11W  
CN  $\frac{1}{2}$  SE SW  
330' fr NL 660' fr EL SE  $\frac{1}{2}$  SW  $\frac{1}{2}$

Total Depth. 3766'  
Comm. 4-20-40 Comp. 5-15-40  
Shot or Treated. 5-16-40 8000 Gals, Acid  
Contractor. Mabee O.G.Co.  
Issued. 6-22-40

County. Stafford



CASING:  
10  $\frac{3}{4}$ " 250'  
7" 3703'

Elevation.

Production. Pot. 5686 B.

Figures Indicate Bottom of Formations.

shale & sand	150
red bed & shells	667
red rock & lime	880
shale & shells	1251
shale & lime	1480
lime	1674
shale & lime	1930
lime	1990
shale & lime	2080
shale	2150
lime	2160
shale & lime	2875
lime	3165
shale	3182
lime	3197
shale & lime	3351
lime	3611
shale & lime	3702
lime Viola-pay	3766
Total Depth.	

Potential 5686 B., prorated 50 B.

Viola lime 3700-43 good saturation  
Viola lime 3743-53 cherty  
Viola lime 3753-66 good saturation

Cored 3685-3702

5-16-40 acidized w/8000 gals-  
made 66 Bbls hr thru 2 7/8"  
tubing before acid-made 50 Bbls  
hr thru 1/2" choke after acidizing

3762' 2 7/8" Upset tubing in hole

Note: all measurements taken 6'6"  
above casinghead - or from top of  
rotary table.