

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


2-24-11W ✓

Company - H. A. HERSHFIELD & CO., INC.  
Farm - M. Volker No. 1

SEC. 2 T. 24 R. 11 W  
CE/2 NE NE

Total Depth. 3751' PB 3740 $\frac{1}{2}$ '  
Comm. 1-5-45 Comp. 1-26-45  
Shot or Treated.  
Contractor. Pulse-Hershfield Drlg. Co., Inc.  
Issued. 7-28-45

County. Stafford  
KANSAS



CASING:

10 3/4" 268' Cem.  
5 1/2" 3726' Cem.

Elevation. \_\_\_\_\_

Production. Pot. 15 BO,  
plus 40 BW

Figures Indicate Bottom of Formations.

surface & sand	130
shale & sand	225
red rock	520
anhydrite	548
shale	797
salt & shells	1023
shale & shells	1430
lime brkn	1565
shale & shells	1661
lime	1694
lime & shale	1884
lime	1935
lime & shale	2020
lime brkn	2170
shale & shells	2229
lime brkn	2340
shale & shells	2482
sand & shale	2516
shale	2703
sand	2731
lime	3049
shale & shells	3358
lime	3487
lime brkn	3534
lime	3569
lime brkn	3588
lime	3664
shale	3685
lime	3690
shale	3706
sand	3714
shale	3726
Viola lime	3751
Total Depth.	

Drilled-in w/cable tools to T.D.  
of 3751. Plugged back to 3740 $\frac{1}{2}$ '.  
Acidized 500 gals. Swbg. 30 BOPH  
25% wtr.