

SIDE TWO

Operator Name Striker Petroleum Corporation Lease Name Zenith Unit Well # 37

Sec. 2 Twp. 24 Rge. 11 East West County Stafford

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No

Formation Description
 Log Sample

Name	Top	Bottom
Misener	3678	3692
Viola	3695	TD

	Oil	Gas	Water	Gas-Oil Ratio	Gravity
Estimated Production Per 24 Hours	60 Bbls	TSTM MCF	1429 Bbls	CFPB	40

METHOD OF COMPLETION

Production Interval

Disposition of gas: Vented Open Hole Perforation
 Sold Other (Specify)
 Used on Lease

3678-3735

RECEIVED STATE CORPORATION COMMISSION Dually Completed Commingled

APR 17 1986

CONSERVATION DIVISION
 Wichita, Kansas
 CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	23	213	CI A	175	3% CaCl ₂
Production	7 7/8	5 1/2	15.5	3806	RFC	165	

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record

Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth
2	3730-3735	750 gal 15%	
2	3695-3702	750 gal 15%	
2	3678-3684	500 gal 15%	

TUBING RECORD Size 2 7/8 Set At 3709 Packer at _____ Liner Run Yes No

Date of First Production March 8, 1986 Producing Method Flowing Pumping Gas Lift Other (explain).....



2-24-11W^p

Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

February 19, 1986

X
Incl

COMPANY: STRIKER PETROLEUM CORPORATION

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: Zenith Waterflood Unit #37

LOCATION: 100 North & 1320' West SE Corner
Approx. S/2 S/2 Section 2-24-11W,
Stafford County, Kansas

COMMENCED: February 11, 1986

COMPLETED: February 18, 1986

ELEVATION:

APR 21 1986
KANSAS REAL ESTATE COMMISSION
WICHITA BRANCH

0	to	165	Sand
165	to	1515	Shale
1515	to	2645	Shale & Lime
2645	to	3063	Lime & Shale
3063	to	3807	Lime
		3807	T. D.


Cut 12 $\frac{1}{4}$ " hole to 213' and run 215' of 8 5/8" surface casing, cemented with 175 sacks of cement at 213'. Plug down at 6:45 P. M., February 11, 1986. Run 3813' of 5 $\frac{1}{4}$ " casing, cemented with 165 sacks of cement at 3806'. Plug down at 2:25 A. M., February 18, 1986.

TOPS:

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Zenith Waterflood Unit #37, located on 100' North & 1320' West of SE Corner Approx. S/2 S/2 Section 2-24-11W, Stafford County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 CHARLES D. JOHNSON, SECRETARY-TREASURER