

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk Bldg., Wichita, Kansas


3-24-11W

GREAT LAKES CARBON CORP.
 Buckles No. 1.

SEC. 3 T. 24 R. 11 W
 CE 1/2 SE NW

Total Depth. 3730'
 Comm. 12-14-42 Comp. 1-12-43
 Shot or Treated.
 Contractor. Crow Drig. Co.
 Issued. 3-20-43

County. Stafford



CASING:
 8 5/8" 324'
 5 1/2" 3700'

Elevation.

Production. Pot. 513 B. Phy.

Figures Indicate Bottom of Formations.

surface clay	30
sand	190
red rock	295
shale & shell	532
anhydrite	570
shale & shell	1109
salt	1405
shale	1414
anhydrite	1426
shale & shells	1465
anhydrite & shale	1515
shale & lime	1627
shale	1641
lime cherty	1670
brkn lime & shale	1742
lime & shale	1810
lime brkn	1845
lime & chert	1867
lime & shale	2032
lime	2052
lime & shale	2083
lime & chert	2094
lime & shale	2122
shale & shells	2209
shale & lime	2695
shale & shells	2789
shale & lime	2900
lime brkn	2970
lime	3041
lime brkn	3121
lime	3171
lime brkn	3380
lime	3384
lime & cherty	3475
lime	3670
lime & cherty	3700
Viola dolomite	3730
Total Depth.	

Geological Data:
 Top Viola 3695