


3-24-11W

GREAT LAKES CARBON CORP.
 Johnson No. 1.

SEC.3 T.24 R.11W
 CE $\frac{1}{2}$ SW NE

Total Depth. 3735'
 Comm. 1-13-43 Comp. 2-14-43
 Shot or Treated. 3000 Gals. Acid
 Contractor. Crow Drlg. Co.
 Issued. 3-27-43

County. Stafford



CASING:
 8 5/8" 243'
 5 1/2" 3693'

Elevation.

Production. Phy. Pot. 160 B.

Figures Indicate Bottom of Formations.

clay	28
sand	180
shale red	527
anhydrite	563
shale & shells	1100
salt	1235
lime brkn	1361
shale	1418
anhydrite	1443
lime	1483
lime brkn	1639
lime	1663
lime cherty	1672
lime	1704
lime & shale	1789
lime brkn	1835
lime sdy cherty	1861
lime	1879
shale & lime	1944
lime	1987
shale	2046
lime	2059
lime & shale	2088
lime cherty	2094
lime	2104
lime & shale	2547
lime brkn	2601
lime	2637
shale	2654
lime & shale	2727
shale	2805
shale & lime	2880
lime	3179
lime & shale	3327
lime	3383
lime cherty	3468
lime	3644
lime cherty	3675
shale	3691
chert	3693
lime cherty	3696
lime Viola	3735
Total Depth.	

Tops:
 Lansing 3330
 Viola 3691