

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


8-24-11W

Company - TRANSWESTERN OIL COMPANY
Farm - Nellie Kelly No. 1

SEC. 8 T. 24 R. 11 W
NE NW SE

Total Depth. 3841' FB 3752'
Comm. 6-15-44 Comp. 8-15-44
Shot or Treated.
Contractor.
Issued. 2-3-45

County. Stafford
KANSAS



CASING:

9" 260' Cem.
5½" 3789' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	120	11 BBl. 0 & 28 BBl. wtr.
red rock & shells	286	in 12 hrs. On 22 hr. pmpng
red bed, shale & shells	555	test-14 B0 & 45 BW.
anhydrite	585	chert & lime 3808-18
shale & shells	1105	chert & lime, wh dolo 3818-21
salt & shells	1430	chert & lime, less dolo 3821-33
salt & shale	1470	lime & chert, no sh. 3833-41 T. D.
lime & shale	1700	Lane-Wells perforated from
lime brkn	1805	3802-3806 w/24 -9/16" B.
lime	1845	No increase in fluid/
lime brkn	1967	Run tbg. & acidized with Jet
lime & shale	2060	Gun
lime brkn	2241	Well tested 1 BBl. PH, 90% wtr
lime & shale	2641	Acidized w/1000 gal. acid
lime brkn	2741	w/pilot set @3801'
lime	2960	Well tested 10 BBl. wtr in
lime brkn	3082	8 hrs.
lime	3250	Swabbed well thru tbg. 8 hrs., 10
shale & lime	3286	BBl. wtr., 1 BBl. Oil
lime	3340	Plugged back to 3752'
lime & shale	3450	
lime brkn	3500	
cherty lime	3530	Tops:
lime brkn	3706	K. C. Lime 3400
shale	3791	Misner Sand 3768
		Shale Sandy to 3772
		Viola Lime 3787

T. D. w/rotary 3791
Cable Tools
Drilled Shoe @3790
lime wh hrd, small show
of oil. Hole filled 200'
6 B. clear wtr, 2½ B. oil
tested approx. 8 Gal. PH
0 & wtr. 3790-93
lime wh hrd, after setting
over night, 3½ BW (2BBl.)
2½ B0 (1½ BBl.) 3793-94
chert hrd 3794-96½
lime & chert sft.
slight stain 3796½-98
chert & lime hrd,
tested approx. 7 gal. PH
30% wtr. 3798-99
Hole filled 200' over-
night, 60% wtr, acidized w/1000

When well was abd 1455' of
5½" OD 14# 8 Rd. Thd. Casing was
recovered.

gal. Hole swbbed to btm
would fill 125' betwn
runs of swab. approx.
30 min.
Swabbed well 8 hrs.-28
BBl. fluid, 50% wtr
After head was off, averaged
13/4 BBl. PH 50% wtr
chert & lime, slight
stain, wh Dolo. 3799-3802
cherty lime, stain 3802-06
cherty lime, no sh. 3806-08½
Acidized with 1500 gal.

pmpng test first 12Hrs.