

8-24-11W

Company - WILLIAM GRAHAM OIL CO.

Farm - Waples

No. 1

SEC. 8

T. 24

R. 11W

NE SW NW

Total Depth. 3788

Comm. 2-28-50

Comp. 3-11-50


Shot or Treated.

Contractor. William Graham Oil Co.

Issued. 4-15-50

County. Stafford

KANSAS



Elevation. 1834 RB 2nd

Production. Dry

CASING:

8 5/8" surface 173' cem. w/100 sx.
 5 1/2" 3799' cem. w/50 sx.

Figures Indicate Bottom of Formations.

surface clay	30
sand	40
sand & shale	130
red bed & shale	624
anhyd.	639
shale & shells	1500
shale & lime	1734
lime	1860
shale & lime	2125
lime	2155
shale & lime	2615
lime sdy	2655
lime & shale	2938
lime	2980
shale & lime	3010
lime	3255
lime & shale	3401
lime	3722
lime & shale	3755
shale	3775
lime RTD	3784
cherty dolo.	3788
Total Depth	

Tops:

Viola chert dolo. 3778

7 gal. wtr. / 1 gal. dead oil.