


9-24-FW

CHAMPLIN REFG. CO.
Figger No. 1.

SEC. 9 T. 24 R. 1W
GEL SE NE
660' N SL 330' W EL NE $\frac{1}{4}$

County. Stafford

Total Depth. 3815'
Comm. 6-23-41 Comp. 7-6-41
Shot or Treated.
Contractor.
Issued. 9-20-41 Rotary O-3815



CASING:
8 1/4" 300' Cem.
4 1/2" 3785' 11" Cem.

Elevation.

Production. Pot. 6566 B. Echo.

Figures Indicate Bottom of Formations.

sand & red bed	305
red bed	375
shale & red bed	550
anhydrite	580
shale	1000
lime shells & shale	1150
salt & shale	1215
shale & shells	1490
shale & lime	1595
lime	1650
shale	1700
lime	1865
shale & shells	1905
lime	1950
shale & lime	2305
shale	2695
shale & lime	2795
lime	2825
shale & brkn lime	2910
shale & lime	2990
lime	3180
lime & shale	3290
shale	3390
shale & lime	3445
shale, lime, chert	3480
lime	3730
lime & shale	3765
lime	3785
cored	3789
lime	3790
cored	3801
lime	3802
cored lime & dolomite	3811
lime	3815
Total Depth.	

Top Viola 3782