

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


9-24-11W

Company - CITIES SERVICE OIL CO.
Farm - Figger No. 1.

SEC. 9 T. 24 R. 11 W
C82 SW NW
660' N 990' E W 1/4 Cor.

Total Depth. 3784 = 3781 SIM
Comm. 2-13-44 Comp. 2-26-44
Shot or Trsted. No
Contractor. Corbett-Barbour Drig.Co.
Issued. 5-6-44

County. Stafford
KANSAS



CASING:
8 5/8" 255' Cem.
5 1/2" 3776' Cem.

Elevation.

Production. BHP Gauge Pot.3000
oil, no wtr; Ind.Cap.4833 B.

Figures indicate Bottom of Formations.

surface sand	0-100
red bed & shells	400
shale & shells	955
lime shells & shale	1260
shale & shells	1445
lime brkn	1565
shale & lime	1710
lime	1775
lime & shale	1920
lime	2075
lime & shale	2195
lime	2250
shale	2525
shale & lime	2860
shale	2910
lime	3468
chert	3480
lime	3545
lime & shale	3707
shale	3733
shale & lime	3781
lime	3784

3784 Rot.TD = 3781 SIM
Total Depth.

Corr. Top Viola 3774
Penetration 7

Fillup: 3000' oil in 4 hrs
Hole full oil in
9 1/2 hrs