

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

10-24-11W


STANOLIND OIL & GAS CO.
R.V. Richardson No. 7.

SEC. 10 T. 24 R. 11W
CS $\frac{1}{2}$ N $\frac{1}{2}$ NW
1650' N SL 1320' E WL NW $\frac{1}{4}$

Total Depth. 3800'
Comm. 4-15-41 Comp. 5-22-41
Shot or Treated.
Contractor.
Issued. 8-2-41

Rotary O-3756
Cable 3756-3800

County. Stafford



CASING:
8 5/8"
5 1/8"

269' 5" Cem.
3739' 11" Cem.

Elevation.

Production. Phy. Pot. 73 B.
43 BW

Figures Indicate Bottom of Formations.

cellar	5' 1"
clay	25
sand	130
shale	315
red bed	528
anhydrite	560
shale	830
shale & lime shells	1100
salt	1175
shale & lime	1620
lime brkn	1695
lime & shale	1815
lime brkn	1910
lime brkn & shale	1990
lime & shale	2127
shale	2307
shale & lime	2453
shale	2611
lime brkn	2735
shale	2900
lime brkn	2945
shale & lime	3015
lime	3253
shale & lime	3354
shale	3400
lime	3679
shale	3738
dolomite	3759
lime	3779
dolomite	3781
lime	3786
dolomite	3800
Total Depth.	

Viola 3738-3800

At T.D. 3756 and after initial
1000 Gals Acid treatment, well
made 2 $\frac{1}{2}$ BOPH
Initial physical potential
73 BO, 43 BW