

10-24-11W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

STANOLIND OIL & GAS CO.
R.V. Richardson No. 10.

SEC. 10 T. 24 R. 11W
CW $\frac{1}{2}$ NW SW
1980' N SL 330' E WL SW $\frac{1}{4}$

Total Depth. 3829'

Comm. 7-1-41 Comp. 7-22-41


Shot or Treated.

Contractor.

Issued. 10-25-41

Rotary O-3826
Cable 3826-29

County. Stafford



CASING:

8 $\frac{5}{8}$ " 263' 6" Com.

5 $\frac{1}{2}$ " 3801' 0" Com.

Elevation.

Production. Pot. 1445 B. BHPB
no wtr

Figures Indicate Bottom of Formations.

cellar	4' 7"
sand & gravel	168
clay	300
red bed & shale	545
anhydrite	575
shale	1105
salt	1160
shale & shells	1550
lime brkn	2215
shale	2450
sdv lime	2495
shale & lime shells	2640
lime brkn	2720
shale	2800
lime	2835
shale	2890
lime brkn	2940
lime	3260
shale	3425
lime	3725
shale	3760
shale & lime	3800
lime	3809
lime & chert	3829
Total Depth.	

Viola lime 3799-3829

Swabbing test from btm
averaged 10 BOPH, no wtr, for
3 hrs. Acidized - Flowing
test thru 1" choke averaged
26 BOPH, no wtr, for 3 hrs.
BHPBP 1445 Bbls oil, no wtr
Flowing thru 1" choke, 1/4 open,
flowed 70 BO in 4 hrs.