

1st log plotted by G.E.J.
11-24-11W


STANCLIND O.G. CO.
A. Fuller No. 3

SEC 11 T. 24 R. 11W.
NE SE SW
990' N of S.L. 2310' E of WL.

DEEPENING RECORD

Total Depth. 3816'
Comm. 9-6-38 Comp. 10-4-38
Shot or Treated. 2000 gal acid.
Contractor.
Issued. 12-13-41

County Stafford.



CASING. Rotary 0-3750'
Cable 3750-3816
103/4" 257'8"
6" 3748'

Elevation.

Production. Pot. 1375.
2nd Pot.

Figures Indicate Bottom of Formations.

sand & clay 185
red bed 258
red bed and sand 525
anhydrite 537
sand red bed 587
shale blue and shells 794
red bed 870
shale blue 1035
salt and shale 1402
broken lime 1509
broken lime & shale 1626
broken lime 1716
broken lime and shale 1801
lime & shale 1900
lime and shale break 1970
broken lime 2051
lime 2103
broken lime 2164
broken lime and shale 2255
broken lime 2445
shale and lime shells 2647
broken lime 2806
broken lime & shale 2896
broken lime 2986
lime 3087
broken lime 3161
lime 3190
shale 3198
broken lime 3248
lime and shale brks 3311
shale 3395
lime broken 3521
lime 3569
lime and shale breaks 3625
broken lime 3704
Top Lansing. 3380
shale 3746
chert 3750

Core No. 4. 6'6" Rec. 3762-3768

sand med hard oil and
gas sat.
Top Sand 3762

Core No. 5 3'3" Rec. 3768-3771

sand coarse sat. shale 3770
limo donso no sat. 3771
Top Viola 3770
Total Depth 3771

Top Lansing 3380
Top Unconformity 3746
Top sand 3762

Viola lime 3750-3771

bailer test 3/4 bbls oil per hr. 9-30-38

initial potential 1312 oil actual
production.
2nd potential 1375 bbls oil.

DEEPENING RECORD

Comm. 9-19-41 Comp. 9-25-41
Production - BHFB Pot. 1558 BO, no wtr

lime & chert 3771-76
lime 3777
limestone pinkish 3789
limestone gy 3790
lime gy-pinkish 3791
lime 3792
lime & chert 3794
chert 3799
lime & chert 3800
lime 3804
lime & chert 3811
lime 3813
lime & chert 3814
lime 3816
Total Depth.

Top Unconformity 3746
Cable tools.
Core No. 1. 0/6" Rec. 3750-3756
cherty limo SSG & O.
Core No. 2 1/2" Rec. 3756-3758
cherty limo S.S.O. & G.
Core No. 3 2 1/2" Rec. 3758-3760
lime wh mod SSO & Gas.
2000 gal acid.
thro 3" EUE Perf. at 3758
SLC 3760-3762

Viola lime 3771-3816
Acidized-Flowing thru 3" tbg - 1st hr
75 bbls-2nd hr 65 bbls-3rd 73 bbls, no
wtr. Btm Hole Pressure Bomb Pot. 1558
Bbls Oil, no wtr - Flowing thru 1" choke
Flowed 135 BO, no wtr, 4 hrs

Acidized w/3000 Gals. Acid