

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Plotted by
11-24-11W

STANLIND OIL & GAS CO.
A. Fuller No. 9.

SEC. 11 T. 24 R. 11W
CW $\frac{1}{2}$ SW SW
660' N SL 330' E WL SW $\frac{1}{4}$

Total Depth. 3822'

Comm. 1-19-40 Comp. 2-21-40

Shot or Treated.

Contractor.

Issued. 4-13-40

Rotary 10-3810

Cable 3810-22

CASING:


10 $\frac{3}{4}$ "

255'9"

7 "

3749'9"

County. Stafford



Elevation.

Production. Pot. 1194 B.
no wtr

Figures Indicate Bottom of Formations.

cellar	10
surface clay & sand	85
shale	160
shale, shells, redbed	265
gravel	285
red rock	400
red bed sandy	520
anhydrite	545
shale & shells	930
shale	1090
shale & salt	1385
anhydrite	1405
shale & lime shells	1506
shale & anhydrite	1598
lime brkn	1872
shale	1910
lime brkn & shale	2260
shale & shells	2357
lime brkn & shale	2557
shale & shells	2646
lime brkn	2647
shale & shells	2655
lime sft	2660
shale	2705
shale & lime shells	2806
lime	2830
shale	2842
shale & shells	2910
lime	3172
shale & shells	3335
shale	3410
lime brkn	3444
lime	3473
shale & lime brkn	3496
chat & shale brks	3507
lime	3580
shale	3600
lime	3655
shale	3737
lime	3740
shale	3749
sand	3752
Ls. (chert strkd)	3770
sand	3775

sand, lime	3782
dolomite	3796
dolomitic limestone	3801
limestone cherty	3810
dolomitic limestone	3822
Total Depth.	

Misener Ls. (Unconformity)
3749-3782
Viola 3782-3822