

Plotted.
E.M.
11-24-11W


STANOLIND OIL & GAS CO.
C.E. Hayes No. 5.

SEC.11 T.24 R.11W
CSL NW SE
1650'N SL 660'E WL SE 1/4

DEEPENING RECORD

Total Depth. 3800'
Comm. 3-5-39 Comp. 3-25-39
Shot or Treated. 2000 Gals. Acid
Contractor.
Issued. 10-11-41 Rotary O-3746
Cable 3746-3800

County. Stafford



CASING:
10 3/4" 236' Cem.
7" 3740' Cem.

Elevation.

Production. Pot. 1454 B.

Figures Indicate Bottom of Formations.

sand & clay	265	(Flow test thru osg) 1st hr	After acidizing - flowing
rod rock	505	85 bbl, 2nd hr 52 bbls, 3rd	test, thru 2" choke, 1/2 open
anhydrite	530	hr 58 bbl, 4th hr 52 bbls,	averaged 78 BOPH, no wtr
red rock	565	5th 52 bbl oil, no wtr	for 2 hrs
shale	890	BHP Pot. 1454 bbls (prod.	Btm Hole Pressure Bomb Pot.
shale & sand	1240	last 4 hrs 148.27 bbls -	3407 BO, no wtr
shale & lime	1470	500 PSI Drawdown)	flowed 165 BO in 4 hrs
sdv lime & shale	1590		allowable 60.60 BPD

DEEPENING RECORD

Viola lime 3765-3800

lime brkn & shale	2140	Comm. 7-28-41 Comp. 7-30-41
shale	2760	Production. Pot. 3407 B.,
lime brkn & shale	2860	no wtr
shale	2870	
lime	2985	
lime brkn	3065	
lime	3125	dolomite fine cryst w/
lime brkn	3165	no sh oil 3765-67
lime & shale	3230	dolomite fine cryst,
shale	3335	slightly cherty 3769
shale & lime	3405	very slight sh oil
lime	3605	dolomite fine cryst lgt
shale	3635	gy, no sh oil 3772
lime	3690	limestone cryst coarse
shale	3740	gy, no show 3774
lime	3750	limestone gy, no show 3775
lime sdv	3753	limestone coarse cryst
sand	3764	pink-gy, no show 3778
shale	3764 1/2	lime coarse cryst gy,
lime Viola	3765	no sh oil 3780
Total Depth.		Core #1 rec 2' 3780-3782

Misener Zone 3740-65 1/2

Core Record:
Core #1 3734-46 8' rec.
shale red & green 3734-40
lime cherty hd, low
porosity, some scattered
shows of oil 3740-46
Core #2 3746-48 1' rec.
lime dense, slight
sh oil 3746-48
Core #3 3748-53 3' rec.
lime cherty hd
dense 3748-50
lime sdv hd fine,
dense, sh oil 3750-53
Core #4 3753-58 4' rec.
sand fine lgt, sh
oil 3753-58
Core #5 3758-61 2' rec.
sand coarse dk,
good sh oil 3758-61
Core #6 3761-63 1 1/2' rec.
sand coarse dk,
good sh oil 3761-63
Core #7 3763-65 2' rec.
sand coarse cryst.,
very good sh oil 3763-64
shale green 3764-64 1/2
lime gy dense
(Viola) 3764 1/2-65
Acidized w/3000 Gals. Acid

Total Depth 3800