

1st log plotted  
by G. E. J.

11-24-11W

STANOLIND OIL & GAS CO.  
Rebeca Sims No. 1

SEC. 11 T. 24 R. 11 W  
S<sup>1</sup>/<sub>2</sub> NE  
330' N SL 330' E WL NE<sup>1</sup>/<sub>4</sub>

DEEPENING RECORD

County. Stafford

Total Depth. 3795'

Comm. 5-5-38 Comp. 6-2-38

Shot or Treated.

Contractor.

Issued. 11-29-41


Rotary 3752

Cable 3795

CASING:

10" 248'5"

6" 3740'



Elevation.

Production. Pot. 1304 B.

No wtr.

Figures Indicate Bottom of Formations.

|                                                     |                                     |                                             |                                        |
|-----------------------------------------------------|-------------------------------------|---------------------------------------------|----------------------------------------|
| sand                                                | 80                                  | lime brkn                                   | 3752 <sup>1</sup> / <sub>2</sub>       |
| shale                                               | 252                                 | Core #2 2/3 <sup>1</sup> / <sub>2</sub> rec | 3752 <sup>1</sup> / <sub>2</sub> -3756 |
| red bed                                             | 490                                 | coarse grained sand, fair                   |                                        |
| anhydrite lime                                      | 518                                 | por, lean sat. oil & gas                    | 3754                                   |
| red bed, shale                                      | 650                                 | cherty hrd tight sand, low                  |                                        |
| red bed                                             | 880                                 | por., slight stain                          | 3755                                   |
| shale & shells                                      | 1104                                | very coarse conglomeratic                   |                                        |
| shale                                               | 1160                                | sand, high por, lean sat.                   | 3755 <sup>1</sup> / <sub>2</sub>       |
| shale, salt                                         | 1339                                | chert white, no show                        | 3756                                   |
| shale                                               | 1370                                | Corr. 3756=3752                             |                                        |
| lime & shale                                        | 1475                                | Top Misener sand                            | 3747                                   |
| lime brkn                                           | 1626                                | Cable Tools                                 |                                        |
| lime & shale                                        | 1665                                | Core #1 2/4 recovery                        | 3752-3756                              |
| lime                                                | 1825                                | sdv limestone                               | 3755                                   |
| shale                                               | 1851                                | shale green lgt                             | 3756                                   |
| lime & shale                                        | 2236                                | Total Depth.                                |                                        |
| lime shale, sdy                                     | 2300                                |                                             |                                        |
| lime                                                | 2390                                |                                             |                                        |
| lime & shale                                        | 2453                                | Misener sand                                | 3747-3756                              |
| shale & lime shells                                 | 2533                                |                                             |                                        |
| lime                                                | 2600                                | Flowed 85 B.P.H. on 2 hr test               | 6-2-38                                 |
| lime & shale                                        | 2665                                |                                             |                                        |
| Top Anhydrite                                       | 485                                 |                                             |                                        |
| lime & shale brkn                                   | 2737                                | <u>DEEPENING RECORD</u>                     |                                        |
| brkn lime                                           | 2793                                | Comm. 11-6-41                               | Comp. 11-12-41                         |
| lime & shale                                        | 2900                                | Production. BHPB draw down Pot.             | 8516 B.                                |
| lime                                                | 3154                                |                                             | no wtr                                 |
| lime & shale brkn                                   | 3170                                |                                             |                                        |
| lime & shale                                        | 3260                                | dolomite                                    | 3756-64                                |
| shale & lime brkn                                   | 3326                                | lime                                        | 3784                                   |
| lime                                                | 3371                                | dolomite                                    | 3795                                   |
| SL Correction                                       | 3371=3400                           | Total Depth.                                |                                        |
| lime                                                | 3452                                |                                             |                                        |
| lime brkn                                           | 3490                                | After 3000 Gal. Acid, flowed 35 Bbls 1st    |                                        |
| lime                                                | 3646                                | hr - 35 bbls 2nd hr oil, no wtr             |                                        |
| Top Lansing                                         | 3380                                | 2-stabl. rate BHPB draw down potential      |                                        |
| shale                                               | 3707                                | 8516 bbls oil per day, no wtr - flowed      |                                        |
| shale & lime                                        | 3737                                | 517 bbls - 15 hrs                           |                                        |
| lime                                                | 3745                                |                                             |                                        |
| Core #1 6"/1 <sup>1</sup> / <sub>2</sub> ' recovery | 3745-46 <sup>1</sup> / <sub>2</sub> | Viola                                       | 3756-95                                |
| chert wh, slight sh oil & gas                       |                                     |                                             |                                        |