

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.


PHILLIPS PETROLEUM CO.
J.J. Tretbar No. 6

SEC. 12 T. 24 R. 11W.
CN $\frac{1}{2}$ SW NE

plotted
E.M.
12-24-11W

Total Depth. 3752 DF
Comm. 5-12-41 Comp. 7-16-41
Shot or Treated. 63 shots 3692-3711 6000 gal acid.
Contractor.
Issued. 10-4-41

County Stafford



CASING.

13" 75'
8" 298'
5" 3718'

Elevation.

Production. Pot. 625 B.

Figures Indicate Bottom of Formations.

surface clay and sand	60
sand	130
red bed and sand rock	209
sand and shale	268
red bed	360
sand and shells	530
red bed shale and shells	960
sdv shale and lime	1078
shale and shells	1250
salt and shale	1395
sdv shale	1450
sdv lime and shale	1475
sdv lime hard	1550
sdv lime and shale	1570
sharp sand and shale	1687
shale and shells	1850
lime	1862
sharp hard sand	1935
sand and shale	1972
sand shale and lime	2073
shale and lime	2305
lime	2320
shale and lime	2390
shale	2585
lime and shale	2640
lime	2700
lime and shale	2855
lime	2942
lime and shale	2990
shale	3006
lime and shale	3143
lime	3183
lime and shale	3411
shale	3430
lime pyrite & chert	3456
lime and chert	3469
lime and shale	3490
shale	3526
lime and shale	3545
shale	3590
lime	3650

Top Misener 3692 Sat. in samples.
Cored 3694-3707 and 3712-3746

Top Viola 3717. Slight to good
por. and sat. 3692-3705 and 3718-
3733 and 36 and 3739-52

lime hard	3676
lime and shale	3698
Misener sand	3717
Viola lime	3752
Total Depth. DF.	